

Interactive comment on “Regional-scale brine migration along vertical pathways due to CO₂ injection – Part 2: a simulated case study in the North German Basin” by Alexander Kissinger et al.

Alexander Kissinger et al.

alexander.kissinger@iws.uni-stuttgart.de

Received and published: 9 March 2017

We thank both reviewers for their valuable comments. We will reply to these comments in the following document:

Answers to RC1 comments:

RC1: Vertical exaggeration too small, I do not see topography

Answer: It is true the topography cannot be recognized in Fig. 2, since there is only a difference of 16m. Therefore, we show it in more detail in Fig. 6. We will make this more clear in a revised version.

C1

RC1: The main feature is the fault zone and the corresponding parameters. How is this connected to paper 1? Is this the end of the expert discussions? Why such a high value? This is higher than most saline formations. . .

Answer: It is true we should make a connection here to Part 1. A result of the PM process was to use different transmissivities for the fault zone, which we compared in Fig. 13.

RC1: Justify the reference model. It is missing thermal effects, which provide additional buoyancy.

Answer: We considered the temperature through a constant geothermal gradient which influences the fluid properties like viscosity and density. We agree that thermal effects, resulting from heat transport could play an important role in determining the salinity distribution prior to the injection, especially in regions near the Rupelian Clay barrier where the salinity is still relatively low and temperature effects may dominate (e.g. cold water moving below the Rupelian clay barrier see for example Noack et al. 2013, Kaiser et al. 2013). In a revised version we will therefore discuss this issue.

RC1: Fig. 8: 5 Isolines instead of 6? Please correct number.

Answer: Will be corrected in revised version.

RC1: Describe infinite aquifer BC better. I think it is closed, but at 100 km extra (see also comment further below)

Answer: Will be described in more detail in revised version, also see comment further below.

RC1: Page 18, line 10 ? I do not see this in the Figure. Please be clearer here.

Answer: will be explained better in revised version.

RC1: The upper boundary condition drives the brine through the fault and hydrogeological window into the shallow aquifers and leads to high salinization (up to 50% of

C2

injected brine) in the reference model that is considered as the most likely geological setup (p 12. line 6f). This high leakage rate actually appears as unlikely and already an effect of the BC. Please comment on this a bit more in your manuscript.

Answer: Actually the text on page 12 line 6f states: "All scenarios are evaluated against a reference model. The reference model is not understood as the most likely geological setup, but simply shows all processes under investigation on a recognizable scale." We do not consider this setup to be the most likely, on contrary on page 7 line 23f we state on this matter: "Making a conservative assumption, we assume a permeable vertical pathway along the whole flank of the salt wall and refer to it as a fault zone. This fault zone is a permeable connection between the injection horizon and the shallow aquifers above the Rupelian clay barrier. The assumption of fluid migration via vertical pathways in sediments flanking salt structures is a matter of debate. After LBEG (2012) "the contact zone between salt domes and the CO₂-sequestration horizon is assumed to be a zone of weakness, similar to geological faults". Such zones of weakness may provide effective vertical migration pathways. To our understanding, the assumption of a permeable fault zone along the whole flank of a diapir is an exaggeration of real geological conditions. In contrast, faults of smaller range at shallower depths in the sediments on top of the hanging wall of diapirs may provide pathways for fluids."

RC1: Give Scenario in Figure captions and state varied variable more clearly, that makes it easier to read.

Answer: Will be done in a revised version.

RC1: Sensitivity for Fig. 15 should be calculated using the 2p3c or 1p2c model, not the simplification, which shown to yield wrong results in Fig. 14. Why the model comparison anyway.

Answer: This is true, the 2p3c or 1p2c results should be shown in the figure as well. With this comparison, we wanted to show the importance of including the overburden for estimating far-field pressure propagation. The overburden is not only of importance

C3

with regard to diffuse leakage that may occur, but also in the focused leakage scenario the overburden plays a crucial role due to its effect on the injection horizon diffusivity. The diffusivity decreases by a factor of almost 6 if the overburden is considered as well. We have calculated the diffusivities in Appendix B Table B.1 with the formula given inline on page 28 line 1. We would make this more clear in a revised version of the paper.

RC1: Better scaling of figures (Fig. 14 top left, Fig. 11, Fig. 13, Fig. 16)

Answer: We deliberately always chose the same scale (normalized between 0 and 1). We believe that this makes the figures more comparable among each other. Otherwise differences which are not very large in absolute terms may be overestimated.

RC1: Fig 5 should be drawn using the model area, to indicate the BC clearly. Where are the BC at the salt wall in the 3D model?

Answer: We would do as suggested in a revised version.

RC1: I can see differences in Pressure and fluid mass in 4.2. Please also show salt mass and concentration changes, because that is what is interesting from the point of view of the near surface aquifers. And here, the simulators should be different.

Answer: Maybe there is a misunderstanding. Salt concentration changes and cumulative salt mass are shown in Figures 9 and 10. For the model comparison section we did not show these, as the 1p1c and the Analytical solution do not consider transport as such (except as flow times a constant value). If we would assume a constant concentration at the freshwater-saltwater interface, it would scale with volume flow rates shown in the model comparison section.

RC1: Make a better connection to the first part of the paper also for the parameters and processes assumed important. Was the model complexity also discussed? What was the outcome of the "expert" discussions?

Answer: Indeed, we did not make many connections to Part 1, as in Part 2 we set the

C4

focus on the technical findings and did not want to overload the manuscript with the PM methodology, as in the first draft previously submitted to HESS. However, we generally agree that there should be a better connection. In a revised version we would make more connections to Part 1 in Sections 1,2 and 3 of Part 2, where the geological and numerical model is presented to make it clear that these were influenced by Part 1.

RC1: Clarify maximum salinity in Table 3. kg_NaCl / kg_brine or kg_NaCl / l_brine ?

Answer: It is kg_NaCl / kg_brine as given in Table 3.

RC1: Also concerning the initial salt gradient: I am wondering how the salt gradient at the beginning of the spin-ups can influence the initial salt distribution in the scenario study 1, which is a balance between the impacts of diffusion and gravity? Is there an upper boundary conditions for salt in the spin-ups?

Answer: The initial salt gradient (linear increase of salt with depth) is the initial condition for the initialization run. In the initialization run, a base flow is established in the shallow aquifers by assigning a constant groundwater recharge rate of 100 Åmm/year. This flow is directed towards the rivers shown in Fig. Å6 where a fixed atmospheric pressure is assigned. The initial linear salt distribution changes due to this base flow and upconing of salt occurs near the rivers, see Fig. 8. A more thorough discussion on parameters and processes influencing the salt distribution after the injection run is given in Kissinger (2016).

RC1: Scenario study one: Better state Low/medium/High salinity gradient instead of just low/medium/high.

Answer: Will be done in a revised version.

RC1: Show Fig 10 as table. Instead, a plot of the isolines for the different cases like in Fig. 8 would be very interesting, to see the changes. Maybe for one or two cases this should be possible.

Answer: We think that Fig. Å10 summarizes an important conclusion of this work,

C5

which is that the amount of salt that is being transported into the shallow aquifers due to the injection is strongly influenced by the initial salt distribution prior to the injection. Therefore, we would like to keep this plot, as in a table we think this relation will be less obvious.

RC1: Discussion section: I do not agree that leakage rate is a good indicator. For modellers this is true, but how do you measure and how do you detect? Additionally, as you state yourself, the salt concentrations may be very different, so NaCl-mass flow rates would also be of interest. The same volume of leaked water has a very different impact with high concentration brine as compared to low concentration brine.

Answer: We agree that different NaCl-mass flow rates will have a very different impact. But a notable leakage rate is a necessary requirement for NaCl mass flow rate to occur. The leakage rate is therefore an important information. The uncertainty in determining a realistic salt distribution prior to the injection is very high as many assumptions have to be made and many data points would be necessary for calibrating such a model in order to obtain reliable results. Another possible way of dealing with such uncertainties could be a Monte-Carlo-like approach with simplified methods and assuming a variety of different concentrations.

RC1: I am unhappy about the term "infinite aquifer" boundary, because obviously that is not the case. The Dirichlet case is that one, the "infinite aquifer" case has just a higher volume and thus dampens the pressure response by a larger overall compressibility. The assessment of the BC is important, I agree, but just assuming that 100 km are "infinite" is wrong, as Figure 11 shows. Please use different terms, and better justify the assumption on your BCs. Check e.g. Benisch and Bauer (2013) for an estimation of the connected boundary volume, which can be appended to the model as bulk storage, to represent this case better. These authors actually also found that the low permeability sections contribute just as much to compressibility as the aquifers, so storage is omitted from the model by extending just the aquifers.

C6

Answer: 1. We compared different lengths of the applied domain extension (50, 100 and 150 km) and compared those to the analytical solution by Zeidouni (2012), which assumes a constant pressure at infinite distance from the injection. We have attached a section from the dissertation Kissinger (2016) describing this comparison. We found that 100 km seems to be a sufficient distance to adequately match the results of the analytical solution. 2. We agree that the low permeability sections have a significant contribution to pressure evolution. Since the regular (unextended) model domain already has a large lateral extent (58x39 km), the influence of the low permeable layers is included for a large distance. Simulation test runs showed that a further increase of the low permeable layers did not significantly change the results.

RC1: Discussion: Please do not just cite the Schäfer paper, but also state their findings. This is interesting here.

Answer: We will state their finding with regard to rock compressibility in a revised version.

RC1: Your paragraph on the model comparison and leakage rates (Page 24, line 22) is confusing. Please state more clearly, that the simple model do not capture the leakage rates correctly, as they do not transport salt. The hydrostatic equilibrium is a function of the BC and of the injection rate in your case. Compare Delfs et al (2016) for this effect – you probably would need to include temperature for this in the simulations and look at the Dirichlet case.

Answer: We will rephrase this paragraph in a revised version to make it more clear. We will also include an extra section to discuss the effects of including non-isothermal heat transport.

RC1: "The Analytical Model is therefore a useful tool to quickly assess the consequences of changing certain parameters within the geological model or to obtain conservative estimates on leakage rates over the fault zone" Have you done more than the two model comparison runs to justify this statement? For one model run, the analytical

C7

model does not work, for the other you get a 30% overestimation. A comparison for a range of parameters as in the parameter study would be helpful, to assess the capabilities of the analytical model fully. However, I do agree that these models are very useful. However, because they have many limitations, a clear understanding of these limitations is helpful (but maybe also beyond scope here).

Answer: The analytical solution for Case i) shown in Fig. 15 was only done to demonstrate the importance of the low permeable overburden on the simulation results. We consider the analytical solution for Case ii) to be at least comparable to the numerical simulation results for the "focused leakage" scenario. There are also other analytical solutions which are capable of describing "diffuse leakage" which may be more appropriate for a larger variety of scenarios. We believe that for these kinds of problems utilizing a combination of analytical and numerical models can be a good idea. Analytical models could be used for quick estimates or Monte-Carlo runs whereas more complex numerical models could be used for verifying the analytical models.

RC1: I agree with the conclusions, but they are highly repetitive with the discussion section. How about merging these sections?

Answer: We could remove the conclusions, as they are already in the discussion, which would as a benefit also shorten the paper.

RC1: Mesh too coarse at fault zones. Any grid resolution study? Have you done a grid effect study to test if you capture the right effects? What did you find?

Answer: We have used a discrete fracture model for describing the fault zone, therefore we are able to assign a fracture width, permeability and porosity. We have conducted a grid convergence study for discretization sizes and fault zone parameters similar to the problem presented in this paper with the analytical solution by Zeidouni (2012) and found that 300x300 m was sufficient for determining volumetric leakage rates (see attached excerpt of Kissinger 2016, DISS_Kissinger_Discretization.pdf Sec. 5.4.1). This grid convergence study was done without considering variable-density flow effects.

C8

Our horizontal grid resolution is constant at 300x300 m, while our vertical resolution is smaller and varies between 10 and 160 m depending on the layer. The fault zone has a width of 50 m. This resolution is of course a compromise between accuracy and computational feasibility. Although we did not perform a grid convergence study for salt transport, we have looked at the effect of salt transport with different fault zone volumes and found it to be not very large during the injection when advective forces dominate, at least when compared to other uncertainties within the hydrogeological system (permeabilities, porosities, fault zone implementation at a salt wall flank in general).

The effects of salt transport: The implementation of the discrete fracture model is such that per default a part of the degree of freedom's (DOF) volume is from the fracture and part from the matrix surrounding the fracture. We have looked at the effect when we neglect the matrix part of the volume at the DOF. This results in a reduced volume at the DOF and therefore a decreased DOF porosity (only fracture volume is active) and an increased transport velocity of the salt water being pushed upwards by the injection. This volume reduction can be as high as a factor of 6 (depending also on fracture and matrix porosities). We have attached a figure describing this comparison from the dissertation Kissinger (2016), see below. Please note that in the figure the "reference" case is not the reference case in this manuscript but the $W_m=1$ case corresponds to the reference case in this manuscript. Here we provide a short summary of the results for more details please consider Kissinger (2016). What we see is that as expected the salt transport into the shallow aquifers increases for the reduced porosity case (only fault zone porosity) compared to the default case (matrix and fracture porosity considered at the DOF). The overall volumetric leakage is also reduced which is a result of the increased weight of the fluid column inside the fault zone which leads to an increased resistance against upward flow. A similar behavior of increasing resistance and lower total mass flow rates due to brine being pushed upward in an improperly sealed abandoned well is reported by Birkholzer (2011). However, the increase in salt transport and the decrease in volumetric leakage we observe for our scenario are rather small.

C9

Answers to RC2 comments:

RC2: First of all, the text is still for my impression far too long and the authors should try to shorten it where possible.

Answer: This will be difficult to achieve, as from the comments of RC1 we got the impression that a revised version would need to comment on further issues in the discussion. But we will consider shortening the introduction and the literature review where possible.

RC2: A linkage with the participatory modeling approach (part 1) is missing at all. This should be changed.

Answer: Indeed, we did not make many connections to Part 1, as in Part 2 we set the focus on the technical findings and did not want to overload the manuscript with the PM methodology, as in the first draft previously submitted to HESS. However, we generally agree that there should be a better connection. In a revised version we would make more connections to Part 1 in Sections 1,2 and 3 of Part 2, where the geological and numerical model is presented to make it clear that these were influenced by Part 1.

RC2: The motivation to identify a setup with a minimum of computational cost while delivering a maximum of valuable results is understandable. However, it should be emphasized that every simplification leads to a loss of accuracy. If this is kept in mind it is absolutely okay to use these somewhat simplified models for understanding the occurring processes and for obtaining estimates.

Answer: We will try to make this more clear in the discussion of a revised version.

RC2: I do understand that the study shows that it seems to be okay to neglect buoyancy effects for this model. However, for this finding maybe more simple box model studies (with comparisons to experiments) would be a more straight forward approach. Also, the number of simplifications is quite accumulated, keeping in mind that the effect of CO₂ (two phase flow) is neglected in the first.

C10

Answer: The point we try to make is that if we are interested in a realistic distribution of salt for estimating concentration changes due to CO₂ injection it is very important to know about the baseline salt distribution prior to the injection of CO₂. Having a model capable of describing the natural conditions prior to the injection is very much dependent on variable-density transport of salt and possibly also heat. During the injection phase however our results suggest that the effects of variable-density flow are less relevant as advective forces due to the injection dominate.

RC2: The conclusions are mainly banal.

Answer: We could remove the conclusions as suggested by RC1, as they are already in the discussion, which would as a benefit also shorten the paper.

RC2: Buoyancy effects due to temperature are not discussed. Peclet numbers (temperature and concentration) and Rayleigh numbers (occurrence of free convection) are not discussed.

Answer: We understand that the effects of heat transport can be an important issue for establishing a natural state of the system prior to the injection or even during the injection phase, although presumably to a lesser extent as advective forces will dominate here. We will discuss this issue in a revised version.

RC2: The study is about injecting CO₂ into the middle Buntsandstein in the North German Basin. However, it is well known that the Buntsandstein is under very high formation pressure (more than 600 bar). Have the authors considered the extreme effort of pumping CO₂ in to such an overpressurized formation, for instance by considering the energy consumption?

Answer: The statement is about the fact, that initial reservoir pressures in Middle Buntsandstein gas fields in NW Germany are relatively high (over-pressured regime). Based on this fact, the reviewer presumes very high absolute formation pressures of over 600 bar in general for Middle Buntsandstein reservoir rock units in the North Ger-

C11

man Basin. That is not true, as formation pressures are of course depth dependent. Known pressure gradients for Middle Buntsandstein gas fields are about 1.3 – 1.5 bar/10m. Hence, in moderate depths (injection point in our model is ca. 1600 m for example) no extreme reservoir pressures are expected. It would be part of a site screening and selection process to choose a suitable site with feasible reservoir conditions. Furthermore, the majority of the Middle Buntsandstein gas fields in NW Germany are located in the Lower Saxony Basin (LSB), which is a part of the North German Basin. The characteristics of those gas fields reflect the geological conditions found in the LSB. This sub-basin represents an inversion play with complex reservoir structures formed during Upper Cretaceous inversion phase. The conditions in the LSB, like e.g. relatively high reservoir pressures in the Middle Buntsandstein, should not be extrapolated to the entire North German Basin in a simple manner.

RC2: Page 25, Line 7 – 8, this sentence seems to be wrong

Answer: Will be rephrased in revised version.

Literature:

Birkholzer, J. T., Nicot, J. P., Oldenburg, C. M., Zhou, Q., Kraemer, S., & Bandilla, K. (2011). Brine flow up a well caused by pressure perturbation from geologic carbon sequestration: Static and dynamic evaluations. *International Journal of Greenhouse Gas Control*, 5(4), 850-861. DOI: 10.1016/j.ijggc.2011.01.003

Kaiser, B. O., Cacace, M., and Scheck-Wenderoth, M. Quaternary channels within the Northeast German Basin and their relevance on double diffusive convective transport processes: Constraints from 3-D thermohaline numerical simulations. *Geochemistry, Geophysics, Geosystems*, 14(8):3156–3175, 2013.

Noack, V., Scheck-Wenderoth, M., Cacace, M., and Schneider, M. Influence of fluid flow on the regional thermal field: results from 3D numerical modelling for the area of Brandenburg (North German Basin). *Environmental Earth Sciences*, 70(8):3523–

C12

3544, 2013.

Kissinger, A.: Basin-scale site screening and investigation of possible impacts of CO₂ storage on subsurface hydrosystems, 2016. doi: <http://dx.doi.org/10.18419/opus-8998>. URL <http://elib.uni-stuttgart.de/handle/11682/9015>

M. Zeidouni. Analytical model of leakage through fault to overlying formations. *Water Resources Research*, 48(12):n/a–n/a, dec 2012. ISSN 00431397. doi: 10.1029/2012WR012582. URL <http://doi.wiley.com/10.1029/2012WR012582>.

Please also note the supplement to this comment:

<http://www.hydrol-earth-syst-sci-discuss.net/hess-2016-687/hess-2016-687-AC1-supplement.pdf>

Interactive comment on *Hydrol. Earth Syst. Sci. Discuss.*, doi:10.5194/hess-2016-687, 2017.

C13




Figure 5.20.: **Left:** Volumetric flow normalized by injection rate into target aquifers through the fault zone. **Right:** Salt flow into target aquifers through fault zone.

Fig. 1.

C14